BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED SCHEDULE –'B'

Name of Work:-Drilling of Borewells and Providing Pipelines in Ward No. 03.

Sl	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
1	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its qualityf 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging techinical personal and labour required etc., as per Specification and direction (P.48, I. 9.4) PRED.SR 2012-13	Each BW	4	1938.46	Rueeps one thousand nine hundred thity eight and paise forty six only
2	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,) P. 46 / I. 9.1 PRED SR 2012-13	Rmtr			
	0 to 50 m		200.00	315.18	Rupees three hundred fifteen and paise eighteen only
	50 to 100 m		200.00	412.00	Rupees four hundred twelve only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

	100 to 150 m		200.00	458.35	Rupees four hundred eight and paise thity only
	150 to 200 m		200.00	484.10	Rupees four hundred eighty four and paise ten only
	200 to 250 m		200.00	560.32	Rupees five hundred six and paise thirty two only
	250 to 300 m		200.00	600.49	Rupees six hundred and paise forty nine only
	300 to 350 m		200.00	640.66	Rupees six hundred forty and paise sixty six only
3	Supply of ISI mark 175 mm nominal bore, Plain end steel casing pipe - grade of Steel Fee 410 of wall thickness 5.4mm thick confirming to IS 4270:2001 and latest amendments, electric resistance welded steel tube material and confirming to IS 1387/1993 and manufactured by baseic open hearth electric or basic oxygen process in random length of 5 to 7 mts both ends threaded confirming tio IS 554/1985, one end fixied with socket confirming to IS 4270:2001 and the other end with screwed pipes ISI Marking weighing 25.10Kg/mtr (Inclusive of all taxes and durties) Prices include Collar-medium duty **P. iii, I No. 84 PRED SR 2012-13**	Rmtr	300.00	1325.00	Rupees one thousand three hundred twenty five only
4	Providing 250mm dia PVC Pipe 6kg/cm **BWSSB SR 2014-15 Page No. 53, Item No. 1(ii)**	Rmtr	72.00	1100.00	Rupees one thousand one hundred only
5	Providing and fixing 160mm Borewell Cap **P. iii, I No. 85 PRED SR 2012-13**	Each	4	100.00	Rupees one hundred only
6	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings 12.50 HP 25 stage. ATALANTA< SUGNA< CRI, KIRLOSKAR and other Equivalent Pumps **PWD SR 2015-16 P. XXXX Item No. 24 including of all taxes 12.5 HP 25 Stage**	No	4	60400.00	Rupees sixty thousand four hundred only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

	3.6 : Providing and fixing in trenches galvanised / mild steel tubes dium grade) 50mm dia nominal bore with all fittings (earth work in trenches to e measured and paid for separately) including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.14 / 13.6 **Page No. 89, Item No. 13.15 PWD SR 2016-17**	m	1120.00	457.92	Rupees four hundred fifty seven and paise ninety two only
8	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100Volts as per IS-694:1990 & confirming to GTP of **GROUP-A. P. No. 12 / I No. 2.10.4(1) 3C x 4 Sqm mm KPWD Electrical SR**	Mtr	2320.00	126.70	Rupees one hundred twenty six and paise seventy only
9	Labour charges for erection as new /repaired submercible pumpset allong with GI pipe (32/50mm) cable (new submercible pumpset if required will be supplied by the department free of cost and released pumpset shoud be handed over to department including transportation (Each lenth =6.00) **Page No. 558, Items No-3 BWSSB SR for 2014-15)**	Per Length	196.00	88.00	Rupees eighty eight only
10	Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., **P No. 44 / I No. 6.6.6 KPWD Electrical SR 2014-15**	Each	4	302.00	Rupees three hundred two only
11	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A **P No. 55/ I No. 7.4.4 4 core 16 Sqmm KPWD Electrical SR 2014-15**	Mtr	160	140.40	Rupees one hundred forty and paise forty only
12	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.In existing trench/duct. **P No. 61 / I No. 7.8.1 6Sqmm to 16 Sqmm) KPWD Electrical SR 2014-15**	Mtr	160.00	10.80	Rupees ten and paise eighty only
13	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete.(As per Civil SR KSRB I-2, P-7) **P No. 61 / I. No. 7.9.3 KPWD Electrical SR 2014-15 For Cutting Road Surface**	Mtr	140.00	85.00	Rupees eighty five only
14	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV **P. No. 62 / I No. 7.12.1 KPWD Electrical SR 2014-15**	Mtr	16.00	345.00	Rupees three hundred forty five only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

15	Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., **P. No. 62 / I.No. 7.13.2 KPWD Electrical SR 2014-15 16Sqmm**	No.	4	280.00	Rupees two hundred only
16	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia, **(P No. 55, I No. 7.1) KPWD Electrical SR 2014-15**	No	4	2727.00	Rupees two thousand seven hundred twenty seven only
17	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers.**P No. 44 / I No. 6.7.2 KPWD Electrical SR 2014-15 32 Amps**	No.	24	180.00	Rupees one hundred eighty only
18	KSRB13-7.1-4 : Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.10 / 13.13 **Page No. 93, Item No. 13.55, PWD SR 2016-17**	Nos	4	1585.76	Rupees one thousand five hundred eighty five and paise seventy six only
19	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete.- **for 50mm dia: Page No. 95 , Item No. 13.81.3 PWD SR 2016-17 50mm dia**	Each	4	227.90	Rupees two hundred twenty seven and paise ninety only
20	Supplying and fixing 50mm dia GI X nipple with ISI mark with all lead and lift loading unloading and labour charges etc complete **P. XXXVII PWD SR 2016-17**	No	16	104.30	Rupees one hundred four and paise thirty only
21	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. **5-32Amps Group A TPN P No. 47 / I No.6.16.5 KPWD SR 2014-15**	No	4	1547.00	Rupees one thousand five hundred forty seven only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

	...ing supplying and mounting MS box made out ... SWG suitable for floor / ... mounting, fully weather proof with provision for better heat dissipation, ...rovided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete **P.No. 57, I. No. 6.41.2 KPWD Electrical SR 2014-15 16SWG**	Sq.Cm	96600.00	0.33	Paise thirty three only
23	Supplying fully automatic store detta starter unit push button type with suitable wires three contractors one adjustable termal timer mounted on a common base plate held in steel enclosure for use on 400/440 volts 3pase and wired offter fixing to the wooden board for motor upto **12.50 HP (KPWD electrical SR for 2014-15 Page No. 44 Item No. 6.2.1)**	No.	4	6583.00	Rupees six thousand five hundred eighty three only
25	Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including sharing and strutting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strructure manhole. **Page No. 01/ Item No.1.2.2 / PRED SR 2012-13 Hard Soil**	Cum	1331.25	188.00	Rupees one hundred eighty eight only
26	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation	Rmtr	1775.00	157.00	Rupees one hundred fifty seven only
27	KSRRB M1200-46. Sand filling in wells complete as per drawing and technical specifications MORTH Specification No.1207 Page No. 213, **Page No. 26.124, PWD SR 2016-17**	Cum	532.50	2922.49	Rupees two thousand nine hundred twenty two and paise forty nine only
28	Refilling the basement and pipeline treanches with secleted available earthe for trench excavation including authority condition in layers from thedi including disponsary of the sunplus earth with a heavy 200 mtrs **Page No. 3 / Item No. 1.6 / PRED SR 2012-13**	Cum	798.75	61.00	Rupees sixty one only
29	KSRB13-6.3-7 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) **65mm nominal bore** including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.6 / 13.3. **P. No.92 / I. No. 13.38 PWD SR 2016-17**	Each	30.00	2729.50	Rupees two thousand seven hundred twenty nine and paise fifty only

EXECUTIVE ENGINEER-4
KRIDE, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64